

BRUHAT BANGALORE MAHANAGARA PALIKE

SCHEDULE - B

Name of Work: Name of Work: Providing cement concrete road constuction of culverts and RCC drains and Providing missing covering slabs in Kateramma Layout and surrounding areas in ward no:10

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M/s KRIDL	
				In Figures	In Words
1	646.44	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(P.No-143 &136 ,I No-19.1&17.4&17.1)	Cum	207.60	Rupees Two Hundred Seven and Sixty Paise Only
2	322.76	Providing granite 10 cms thick slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete	Sqm	966.72	Rupees Nine Hundred Sixty Six and Seventy Two
3	33.03	KSRB 4-1.2 : Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2	Cum	5505.64	Rupees Five Thousand Five Hundred Five and Sixty Four Paise Only
4	10.80	Providing and constructing granite / trap / basalt Size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. and as per the directions of the Engineer-in-charge of the work	Cum	4871.76	Rupees Four Thousand Eight Hundred Seventy One and Seventy Six Paise Only
5	18.00	Providing FLush pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. and as per the directions of the Engineer-in-charge of the work	Sqm	223.66	Rupees Two Hundred Twenty Three and Sixty Six Paise Only
6	64.10	Providing laying plain/ reinforced cement concrete for side Drains Using M20 nominal mix Concrete with OPC at 300kgs.With 20mm and Down size granite metal coarse aggregate at 0.69cum and fine aggregate at 0.43cum Machine mixed, well compacted for wall and Bottom including centering shuttering, cost of materials, HOM of Machinery, Curing Etc., Complete Excluding cost of Steel as per morth MORTH	Cum	7070.20	Rupees Seven Thousand Seventy and Twenty Paise Only
7	4.91	KSRB M2200-6 Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. MORTH Specification NO.1600&2200Specification No. Pg No.229 Item No.28.8.2	Tonne	72326.98	Rupees Seventy Two Thousand Three Hundred Twenty Six and Ninety Eight Paise Only
8	633.33	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of all materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. (Data Rate)	Sqm	2337.00	Rupees Two Thousand Three Hundred Thirty Seven Only
9	109.80	Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of all materials, labour,hire charges of machinery loading unloading lead and lift transportation etc	Sqm	5418.00	Rupees Five Thousand Four Hundred Eighteen Only
10	442.00	KSRRB 300-46. ScKSRRB 300-50. Scarifying bituminous course 50mm to 75mm thick along with premix carpet / surface dressing by mechanical means attached with scarifier without disturbing the base and stacking the debris including cost of all labour charges, HOM complete as per specifications. MORTH / Chapter 3 (P.No-146,I No-19.56)	Sqm	41.34	Rupees Forty One and Thirty Four Paise Only

EXECUTIVE ENGINEER-4
Signature of the contractor
BANGALURU-560 010

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rate	
				M/s KRIDL	
				In Figures	In Words
11	412.87	KSRRB M300-14. Excavation for roadwork in all types of soil by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specifications MORTH Specification MORTH Specification No.301 Loading and unloading with 10km lead= (I No-19.14,P No-143)	Cum	56.26	Rupees Fifty Six and Twenty Six Paise Only
12	44.55	KSRRB M400 Stone dust / Grit 4.75 mm to 0.075 mm For Road Strengthening For UGD Cut portion	Cum	1060.00	Rupees One Thousand Sixty
13	308.05	KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications(P.No-155,I No-20.18)	Cum	2001.28	Rupees Two Thousand One and Twenty Eight Paise Only
14	737.40	KSRRB 500-1.Cleaning the existing WBM Road surface including removing of binding materials and other foreign matter with wire brushes and small picks sweeping with brooms or soft brushes and finally dusting with old gunny bags and bar or compressed air to receive bituminous treatment including cost of all materials, labhour, HOM of machineries complete as per specifications.(P.No.158,I.No.21.1)	Sqm	22.26	Rupees Twenty Two and Twenty Six Paise Only
15	1927.18	KSRRB M500-6. Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications Clause 502 of MORTH V revision(P.No-158,I No-21.6)	Sqm	28.62	Rupees Twenty Eight and Sixty Two Paise Only
16	96.36	KSRRB M500-17. Providing and laying dense graded bituminous macadam using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications Clause 505 of MORTH V revision using 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 4.5 % VG-30 Bitumen (P.No-160,I No-21.17.6)	Cum	6597.44	Rupees Six Thousand Five Hundred Ninety Seven and Forty Four Paise Only
17	4170.53	KSRRB 500-2.Cleaning the existing black topped surface with brooms,soft brushes and finally dusting with old gunny bags and/or compressed air to receive bituminous treatment including cost of all materials,labhour, HOM of machineries complete as per specifications.(P.No.158,I.No.21.12).	Sqm	5.30	Rupees Five and Thirty Paise Only
18	4170.53	KSRRB 500-7. Providing and applying tack coat using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM complete as per specifications (P.No-161,I No-21.7)	Sqm	12.72	Rupees Twelve and Seventy Two Paise Only
19	166.82	KSRRB M500-19. Providing and laying bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications Clause 507 of MORTH V revision using 40/60 TPH capacity H.M.P. with Mechanical Paver Gr-II (30 mm to 45 mm) with 5.4% VG-30 Bitumen(P.No-162,I No-21.22.6)	Cum	7753.90	Rupees Seven Thousand Seven Hundred Fifty Three and Ninety Paise Only

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
Signature of the contractor
BENGALURU-560 010

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				M/s KRIDL	
				In Figures	In Words
20	163.74	KSRRB M800-13.Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface/ Concrete Surface: Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 standards specified. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803(P.No-182,I No-24.15)	Sqm	454.74	Rupees Four Hundred Fifty Four and Seventy Four Paise Only
21	213.82	KSRRB M200-24. Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceable and unserviceable materials seperately complete as per specifications. MORTH Specification No. 202(P.No.140- I.No.18.47) & Pg No.136, Item No.17.4,17.1 (5km lead = 57+2*1.28X5)	Cum	1022.74	Rupees One Thousand Twenty Two and Seventy Four Paise Only
22	160.36	KSRB 4-1.3 : Providing and laying in position plain cement concrete of Mix 1:4:8 with OPC @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2	Cum	5408.12	Rupees Five Thousand Four Hundred Eight and Twelve Paise Only
23	3.23	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggretes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No-13,I No-4.6)	Cum	5747.32	Rupees Five Thousand Seven Hundred Forty Seven and Thirty Two Paise Only
24	160.36	Cement concrete pavement.Construction of un-reinforced plain cement concrete pavement, using a grade concrete M30 over a prepared base with OPC coarse aggregate @ 0.69cum fine aggregate @ 0.46cum,coarse and fine aggregate confirming to IS:383-2016,with superplastisiser @3lts confirming to IS9103-2008mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades, textured with texturing machine,and curing including cost of all materials,labour,hire chargedof machines,all lead and lift charges etc., complete as per specifications. - do with OPC at 360Kg	Cum	5210.96	Rupees Five Thousand Two Hundred Ten and Ninety Six Paise Only
25					

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010
Signature of the Contractor

ಕಾರ್ಯನಿರ್ವಾಹಕ ಇಂಜಿನಿಯರ್
Executive Engineer
Byrangaiah Division
BBMP, Bangalore - 56
ಶ್ರೀಮತಿ. ಕಾರ್ಯನಿರ್ವಾಹಕ ಇಂಜಿನಿಯರ್